

Unit B, 13/F., Universal Ind. Ctr., 23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### TEST REPORT

TITLE

Testing of Pipe Clip

OUR REFERENCE NO.

J8861-27

DESCRIPTION OF SAMPLE

Ø22mm (3/4") Stainless steel pipe clips for parallel multi-pipes (**two to four pipes** respectively); supplied with plastic wall filling device; for BS2871 part 1/BSEN1057 copper pipe; dimensions: 18mm width x 2.5mm thick rings; 20mm width x 5mm thick base plate; with single Ø12mm support stem electrically welded onto the base plate; with 1/4" x 3/4" screws and nuts.

SAMPLE SUBMITTED BY

Cheung's Engineering Co. G/F., 90 Tak Cheong Street, Kowloon, Hong Kong.

**MANUFACTURER** 

Cheung's Engineering Co.

BRAND / LOGO

-

Pipe Clips-

COUNTRY OF ORIGIN

China

TEST REQUIRED

Loading test


PERIOD OF TESTS

20th to 24th January 2003

RESULTS: -LOADING TEST

1. A concrete block made of concrete mix grade 30D10 (cement to BS12: 1978 and Aggregate to BS82: 1973) was prepared and used for the loading test.

2. The plastic wall filling device was connected to the end of a new pipe clip's each support stem.





# NUTEK SYSTEMS, LTD. Unit B, 13/F., Universal 23-25 Shan Mei Street,

Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### REPORT

#### OUR REFERENCE NO.J8861-27 (P.2)

- 3. The concrete block was secured to the loading test frame. A hole was drilled on the concrete block; the pipe clip's support stem was hammered into the hole. A copper pipe of BS2871 part 1 (EN1057) was connected to the pipe clip.
- 4. The evenly distributed vertical pulling force F1 applied to detach the pipe clip from the concrete block was measured.
- 5. Steps 1 to 3 were repeated. A horizontal force F2 applied to the pipe clip (perpendicular to the pipe axis) to result in a 20mm horizontal deflection was measured.
- 6. Steps 1 to 3 were repeated. A horizontal force F3 acting on the pipe along its longitudinal axis to slip the pipe from the pipe clip by 20mm was measured.

#### 7. Result:

Vertical force F1 to detach the pipe clip from the concrete block	Horizontal force <b>F2</b> to result in a 20mm horizontal deflection	Horizontal force <b>F3</b> to slip the pipe by 20mm
(kgf)	(kgf)	(kgf)
380	448	137

Date: 15th February 2003 Authorized signature:

Water Authority and Supplies Department, for testing water supply fittings.

Samson W.K. Yiu



Unit B, 13/F., Universal Ind. Ctr., 23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### TEST REPORT

TITLE : Testing of Pipe Clip

OUR REFERENCE NO. : J8861-28

DESCRIPTION OF SAMPLE : Ø22mm (3/4") Stainless steel pipe clips for parallel multi-pipes (five

to twelve pipes respectively); supplied with plastic wall filling devices; for BS2871 part 1/BSEN1057 copper pipe; dimensions: 18mm width x 2.5mm thick rings; 20mm width x 5mm thick base plate; with two Ø12mm support stems electrically welded onto the base plate;

with 1/4" x 3/4" screws and nuts.

SAMPLE SUBMITTED BY : Cheung's Engineering Co.

G/F., 90 Tak Cheong Street,

Pipe Clips-

Kowloon, Hong Kong.

MANUFACTURER : Cheung's Engineering Co.

BRAND/LOGO :

COUNTRY OF ORIGIN : China


TEST REQUIRED : Loading test

PERIOD OF TESTS : 20<sup>th</sup> to 24<sup>th</sup> January 2003

RESULTS: -LOADING TEST

1. A concrete block made of concrete mix grade 30D10 (cement to BS12: 1978 and Aggregate to BS882: 1973) was prepared and used for the loading test.

2. A plastic wall filling device was connected to the end of a new pipe clip's each support stem.





Unit B, 13/F., Universal Ind. Ctr., 23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### TEST REPORT

#### OUR REFERENCE NO.J8861-28 (P.2)

- 3. The concrete block was secured to the loading test frame. Two holes were drilled on the concrete block; the pipe clip's two support stems were hammered into the two holes respectively. A copper pipe of BS2871 part 1 (EN1057) was connected to the pipe clip.
- 4. The evenly distributed vertical pulling force F1 applied to detach the pipe clip from the concrete block was measured.
- 5. Steps 1 to 3 were repeated. A horizontal force **F2** applied to the pipe clip (perpendicular to the pipe axis) to result in a 20mm horizontal deflection was measured.
- 6. Steps 1 to 3 were repeated. A horizontal force **F3** acting on the pipe along its longitudinal axis to slip the pipe from the pipe clip by 20mm was measured.

#### 7. Result:

Vertical force <b>F1</b> to detach the pipe clip from the concrete block	Horizontal force <b>F2</b> to result in a 20mm horizontal deflection	Horizontal force <b>F3</b> to slip the pipe by 20mm
(kgf)	(kgf)	(kgf)
765	1111	137

Date: 15th Tebruly 2003 Authorized signature:

Nutek Systems is a testing agency, approved by the Water Authority and Government Supplies Department, for testing water supply fittings.

Samson W.K. Yiu



Unit B, 13/F., Universal Ind. Ctr., 23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### TEST REPORT

TITLE : Testing of Pipe Clip

OUR REFERENCE NO. : J8861-29

DESCRIPTION OF SAMPLE : Ø28mm (1") Stainless steel pipe clips for parallel multi-pipes (two

to four pipes respectively); supplied with plastic wall filling device; for BS2871 part 1/BSEN1057 copper pipe; dimensions: 18mm width x 2.5mm thick rings; 20mm width x 5mm thick base plate; with single

Ø12mm support stem electrically welded onto the base plate;

with 1/4" x 3/4" screws and nuts.

SAMPLE SUBMITTED BY : Cheung's Engineering Co.

G/F., 90 Tak Cheong Street,

Kowloon, Hong Kong.

MANUFACTURER : Cheung's Engineering Co.

COUNTRY OF ORIGIN : China

TEST REQUIRED : Loading test


PERIOD OF TESTS : 20<sup>th</sup> to 24<sup>th</sup> January 2003

RESULTS: -LOADING TEST

BRAND / LOGO

 A concrete block made of concrete mix grade 30D10 (cement to BS12: 1978 and Aggregate to BS882: 1973) was prepared and used for the loading test.

2. The plastic wall filling device was connected to the end of a new pipe clip's support stem.





# NUTEK SYSTEMS, LTD. Unit B, 13/F., Universal 23-25 Shan Mei Street,

Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

#### TEST REPORT

### OUR REFERENCE NO.J8861-29 (P.2)

- 3. The concrete block was secured to the loading test frame. A hole was drilled on the concrete block: the pipe clip's support stem was hammered into the hole. A copper pipe of BS2871 part 1 (EN1057) was connected to the pipe clip.
- 4. The evenly distributed vertical pulling force F1 applied to detach the pipe clip from the concrete block was measured.
- 5. Steps 1 to 3 were repeated. A horizontal force F2 applied to the pipe clip (perpendicular to the pipe axis) to result in a 20mm horizontal deflection was measured.
- 6. Steps 1 to 3 were repeated. A horizontal force F3 acting on the pipe along its longitudinal axis to slip the pipe from the pipe clip by 20mm was measured.

#### 7. Result:

Vertical force F1 to detach the pipe clip from the concrete block	Horizontal force <b>F2</b> to result in a 20mm horizontal deflection	Horizontal force <b>F3</b> to slip the pipe by 20mm
(kgf)	(kgf)	(kgf)
380	448	91

Date: 15th February 2003 Authorized signature:

approved by the Water Authority and Government Supplies Department, for water supply fittings.

Samson W.K. Yiu



23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

TEST REPORT

TITLE

Testing of Pipe Clip

OUR REFERENCE NO.

J8861-30

DESCRIPTION OF SAMPLE

Ø28mm (1") Stainless steel pipe clips for parallel multi-pipes (five to twelve pipes respectively); supplied with plastic wall filling devices; for BS2871 part 1/BSEN1057 copper pipe; dimensions: 18mm width x 2.5mm thick rings; 20mm width x 5mm thick base plate; with two Ø12mm support stems electrically welded onto the

base plate; with 1/4" x 3/4" screws and nuts.

SAMPLE SUBMITTED BY

Cheung's Engineering Co. G/F., 90 Tak Cheong Street, Kowloon, Hong Kong.

**MANUFACTURER** 

Cheung's Engineering Co.

BRAND / LOGO

Pipe Clips-

COUNTRY OF ORIGIN

China

**TEST REQUIRED** 

Loading test


PERIOD OF TESTS

20th to 24th January 2003

**RESULTS: -**LOADING TEST

1. A concrete block made of concrete mix grade 30D10 (cement to BS12: 1978 and Aggregate to BS882: 1973) was prepared and used for the loading test.

2. The plastic wall filling device was connected to the end of a new pipe clip's each support stem.





Unit B, 13/F., Universal Ind. Ctr., 23-25 Shan Mei Street, Fo Tan, Shatin, N.T., Hong Kong.

Tel: (852) 2605 5736 Fax: (852) 2692 0798

### TEST REPORT

#### OUR REFERENCE NO.J8861-30 (P.2)

- 3. The concrete block was secured to the loading test frame. Two holes were drilled on the concrete block; the pipe clip's two support stems were hammered into the two holes respectively. A copper pipe of BS2871 part i (EN1057) was connected to the pipe clip.
- 4. The evenly distributed vertical pulling force F1 applied to detach the pipe clip from the concrete block was measured.
- 5. Steps 1 to 3 were repeated. A horizontal force **F2** applied to the pipe clip (perpendicular to the pipe axis) to result in a 20mm horizontal deflection was measured.
- 6. Steps 1 to 3 were repeated. A horizontal force **F3** acting on the pipe along its longitudinal axis to slip the pipe from the pipe clip by 20mm was measured.

#### 7. Result:

Vertical force F1 to detach the pipe clip from the concrete block	Horizontal force <b>F2</b> to result in a 20mm horizontal deflection	Horizontal force <b>F3</b> to slip the pipe by 20mm
(kgf)	(kgf)	(kgf)
765	1111	91

Date: 18th February 2003 Authorized signature:

Nutek Systems is a testing agency, approved by the Water Authority and Government Supplies Department, for testing water supply fittings.

Samson W.K. Yiu